

**SEDGWICK COUNTY SIGN SHOP REMODEL
STILLWELL COMPLEX, BUILDING #16
1015 STILLWELL
WICHITA, KANSAS 67213
PROJECT #05-0077**

ADDENDUM NO. 2

December 19, 2005

NOTICE TO ALL BIDDERS FOR THE

Sedgwick County Appraiser's Office Space Remodel
525 North Main, Second Floor
Wichita, Kansas

You are instructed to read and to note the following described changes, corrections, clarifications, omissions, deletions, additions, approvals and statements pertinent to the Contract Bid and Construction Documents.

The Addendum No. 2 is a part of the Contract Bid and Construction Documents and shall govern performance of the work.

ARTICLE 2-1, SPECIFICATION SECTION 09511

- a. Revise Specification Section 09511 – 2.3 – B to read as follows: **“24 inches long by 24 inches wide by 7/8” thick.**
- b. Revise Specification Section 09511 – 3.2 – A to read as follows: **“Main Runners: Installed 24 inches on center by direct suspension from existing structure, with not less than 12gauge hanger wires, wrapped tightly 3 full turns. Hang system independent of walls, columns independent of walls, columns, ducts, pipes and conduit. Where carrying members are spliced, avoid visible displacement of face plane of adjacent members. Where ducts or other equipment prevent regular spacing of hangers, reinforce nearest hangers and related carrying channels to span extra distance.**