



SEDGWICK COUNTY, KANSAS

DIVISION OF FINANCE

Purchasing Department

604 N. Main, Suite F : Wichita, KS 67203 : Telephone (316) 660-7255 : Fax (316) 383-7055

**Request for Bid
#07-0215
Remodel Jail Storage Room**

Addendum #1

October 26, 2007

The following is to ensure that vendors have complete information prior to submitting a bid. Here are some clarifications for the remodel project of the jail storage room.

Questions and/or statements of clarification are in **bold font**, answers to specific questions are *italicized*.

1. **Change in time zone nomenclature from CDT to CST effective November 4, 2007.**
2. **The following lists hardware items that are to match to existing:**
 - Locks – Model LORI 80 provided by A-1 Locksmith. Contact person is Michael R. Graves. Phone: 316-522-0178. The locks are to be master keyed and set to key AAA-1.**
 - Door Closers – Model LCN4110 manufactured by Ingersoll-Rand.**
 - Door Levers – Model #8822 manufactured by Yale.**
3. **Wire Mesh supplier contact information:**
 - C.E. Shepard (Trish) 800-324-6733**
 - A-Z Consulting and Distributing (Sean Stoddard) 520-749-0544**
4. **In addition to the bronze anodized tube framing as called out in the drawing, black anodized tube framing is also acceptable.**
5. **Does the existing ductwork have a means to balance or will a damper need to be installed in order to balance?**

Answer: Referring to the drawings on sheet M1.1, notes #7 and #8 state that balancing the VAV box and return air ducts to the air quantities shown shall be done by adjusting the diffuser blades in order to provide even and equal coverage throughout the space, thus a damper should not be needed.

6. Are we relocating an existing thermostat or installing a new one?

Answer: *Per note #3 on sheet M1.1 states that the "existing" thermostat and wiring shall be removed and to provide a cover plate over the existing thermostat j-box. A new surface mounted thermostat, wiring and controls shall be installed at a "new location" which is called out to be located on the backside of the center column.*

7. Is the tile to be removed before carpet is laid?

Answer: *The carpet is to be laid over the existing VCT, the contractor will not be responsible for removing glue/tile.*

Firms interested in submitting a bid, must respond with one (1) original and three (3) signed copies of the attached Response Form and deliver **on or before 1:45 p.m. (CST), Tuesday, November 6, 2007** to Sedgwick County Purchasing Department, 604 N. Main, Suite F, Wichita, KS 67203. Late bids will not be accepted and will not receive consideration for final award.

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE BID RESPONSE PAGE.



Joe Thomas, C.P.M.
Senior Purchasing Agent