

ADDENDUM NO. 1

**Sedgwick County Project: 785-B-4588; Bridge on 279th St. West between
109th & 117th Streets North (B455)**


The items contained herein now become a part of the referenced plans and specifications. Please read the following items and acknowledge receipt of this addendum on the Proposal Page Number P-1. NOTE: THIS ADDENDUM MUST BE ACKNOWLEDGED TO CONSTITUTE A VALID BID.

SPECS:

Replace Schedule of Prices sheet SOP-1 to 2 with SOP-1R to 2R.

PLANS:

The correct quantity for the Bridge Backwall Protection System is shown on sheet 27.

By: 
David C. Spears, P.E., Director,
Public Works/County Engineer

Date: August 22, 2014

SCHEDULE OF PRICES

PROJECT: 785-B-4588; Bridge on 279th St. West between 109th & 117th Streets North (B455)

TYPE OF WORK: Bridge, Grading, Surfacing, Signing, Pavement Marking, Seeding, and Guardrail

Bidding Item	Approx. Quantity	Unit	Unit Price	Amount
COMMON ITEMS:				
Contractor Construction Staking	1	Lump Sum		
Field Office	1	Each		
Mobilization	1	Lump Sum		
Removal of Existing Structures	1	Lump Sum		
Restoration of Temporary Easement	1	Lump Sum		
Concrete for Seal Course (Set Price)	1	Cu. Yds.	175.00	
ROAD ITEMS:				
Clearing and Grubbing	1	Lump Sum		
Common Excavation (Rural Small)	1,374	Cu. Yds.		
Common Excavation (Contractor Furnished)	4,628	Cu. Yds.		
Rock Excavation	957	Cu. Yds.		
Compaction of Earthwork (Type AA)(MR-0-5)	1,200	Cu. Yds.		
Compaction of Earthwork (Type A)(MR-5-5)	4,106	Cu. Yds.		
Water (Grading)(Set Price)	1	M. Gal.	35.00	
Guardrail, Steel Plate (MGS)	1,062.50	Lin. Ft.		
Guardrail End Terminal Alt. #1 (MGS-SKT)	4	Each		
Guardrail End Terminal Alt. #2 (MGS-ET PLUS)	4	Each		
Guardrail, Removal of Steel Plate	1,232.25	Lin. Ft.		
CONCRETE SURFACING ITEMS:				
Concrete Pavement (12" Uniform)(AE)	104	Sq. Yds.		
Aggregate Base (Special) (6")	3,529	Sq. Yds.		
ASPHALT SURFACING ITEMS:				
Aggregate Shoulder (AS-1)(7")	722	Sq. Yds.		
Aggregate For Entrances (AS-1)(6")	145	Sq. Yds.		
Water (Aggregate Shoulders)(Set Price)	1	M. Gal.	35.00	
Plant Mix Asphalt Mixture-Commercial Grade (7")	1,211	Ton		
BRIDGE ITEMS:				
Excavation (Class I)	283	Cu. Yds.		
Excavation (Class II)	2,198	Cu. Yds.		
Concrete (Grade 4.0)(AE)	454.0	Cu. Yds.		
Concrete (Grade 4.0)(SA)	1,035.5	Cu. Yds.		
Reinforcing Steel (Grade 60)	87,880	Lbs.		
Reinforcing Steel (Grade 60)(Epoxy Coated)	297,380	Lbs.		
Test Piles (CIP Concrete)(14")	455	Lin. Ft.		
Piles (CIP Concrete)(14")	8,370	Lin. Ft.		

SCHEDULE OF PRICES

PROJECT: 785-B-4588; Bridge on 279th St. West between 109th & 117th Streets North (B455)

TYPE OF WORK: Bridge, Grading, Surfacing, Signing, Pavement Marking, Seeding, and Guardrail

Bidding Item	Approx. Quantity	Unit	Unit Price	Amount
Expansion Joint (Strip Seal Assembly)	76	Lin. Ft.		
Abutment Strip Drain	53	Sq. Yds.		
Bridge Backwall Protection System	92	Sq. Yds.		
Substructure Waterproofing Membrane	66	Sq. Yds.		
Slope Protection (Riprap Stone)(Light 24")	430	Cu. Yds.		
Prestressed Concrete Beam (NU1100+25)	4,052	Lin. Ft.		
Bearing TFE/Elastomeric	12	Each		
Falsework Inspection	1	Lump Sum		
Bridge Deck Grooving	2,427	Sq. Yds.		
SEEDING ITEMS:				
Temporary Seeding	1	Lump Sum		
Temporary Ditch Check (Rock)(Set Price)	1	Cu. Yds.	85.00	
Temporary Ditch Check	40	Lin. Ft.		
Temporary Slope Barrier	2,790	Lin. Ft.		
Sediment Removal (Set Price)	1	Cu. Yds.	35.00	
Mobilization, Emergency Erosion Control (Set Price)	1	Each	1,000.00	
Seeding	1	Lump Sum		
MISCELLANEOUS ITEMS:				
Pavement Marking (Paint)(White)(4")	3,500	Lin. Ft.		
Pavement Marking (Paint)(Yellow)(4")	2,900	Lin. Ft.		
Sign (Flat Sheet) (High Performance)	21	Sq. Ft.		
Signing Object Marker (Type 3)	4	Each		
Traffic Control	1	Lump Sum		
Grand Total				

In Words:

DOLLARS

Company or Firm Name

BY _____

TITLE _____