

ADDENDUM NO. 1

**Sedgwick County Project: 596-25, 26; 93rd St. North between
Meridian & Broadway (R338)**

The items contained herein now become a part of the referenced plans and specifications. Please read the following items and acknowledge receipt of this addendum on the Proposal Page Number P-1. NOTE: THIS ADDENDUM MUST BE ACKNOWLEDGED TO CONSTITUTE A VALID BID.

SPECS:

Replace SOP-1 to 2 with SOP-1R to 2R.

Changing Field Office (Type A) to Field Office (Refer to Special Provision)


Changing quantity for Mailbox Installation (Set Price)

Adding Contractor Construction Staking

Adding Common Excavation (Contractor Furnished)

PLANS:

All changes to the SOP shall be assumed to have been made in the plans.

By: 
David C. Spears, P.E.
Director of Public Works/County Engineer

Date: April 21, 2016

SCHEDULE OF PRICES

PROJECT: 596-25, 26; 93rd St. North between Meridian & Broadway (R338)

TYPE OF WORK: Grading, RCC Surfacing, RCB Culvert, Guardrail, Pavement Marking, Seeding

Bidding Item	Approx. Quantity	Unit	Unit Price	Amount
Field Office	1	Each		
Contractor Construction Staking	1	Lump Sum		
Mobilization	1	Lump Sum		
Clearing and Grubbing	1	Lump Sum		
Removal of Existing Structures	1	Lump Sum		
Common Excavation	3,465	Cu. Yds.		
Common Excavation (Contractor Furnished)	737	Cu. Yds.		
Compaction of Earthwork (Type AA) (MR-3-3)	203	Cu. Yds.		
Compaction of Earthwork (Type B) (MR-90)	3,453	Cu. Yds.		
Riprap (18")	24	Sq. Yds.		
Roller Compacted Concrete Pavement (6" Uniform) (AE)	26,259	Sq. Yds.		
Cementitious Slurry Treated Base (Special)	28,431	Sq. Yds.		
Concrete Pavement (6" Uniform) (AE)	12	Sq. Yds.		
Water (Grading) (Set Price)	1	M. Gal	35.00	
Surfacing Material (AB-3)	219	Tons		
Concrete (Grade 4.0)	56.9	Cu. Yds.		
Concrete (Grade 4.0) (AE)	23.1	Cu. Yds.		
Bridge Backwall Protection System	95	Sq. Yds.		
Reinforcing Steel (Grade 60)	2,250	Lbs.		
Reinforcing Steel (Grade 60) (Epoxy Coated)	11,280	Lbs.		
Foundation Stabilization	28	Cu. Yds.		
Granular Backfill (Wingwalls)	36	Cu. Yds.		
Concrete for Seal Course (Set Price)	1	Cu. Yds.	175.00	
Cross Road Pipe (18") (RCP)	130	L.F.		
Cross Road Pipe (24") (RCP)	94	L.F.		
Cross Road Pipe (5.0 Sq. Ft.) (RCPHE)	40	L.F.		
Entrance Pipe (15") (ACSP)	30	L.F.		
Entrance Pipe (18") (ACSP)	30	L.F.		
Entrance Pipe (18") (RCP)	20	L.F.		
Entrance Pipe (1.5 Sq. Ft.) (ACSMAC)	90	L.F.		
Entrance Pipe (5.0 Sq. Ft.) (ACSMAC)	290	L.F.		
End Section (15") (ACS)	2	Each		
End Section (18") (ACS)	8	Each		
End Section (18") (RC)	2	Each		
End Section (24") (RC)	4	Each		
End Section (1.5 Sq. Ft.) (ACS)	8	Each		
End Section (5.0 Sq. Ft.) (ACS)	4	Each		
End Section (5.0 Sq. Ft.) (RCHE)	2	Each		
Mailbox Installation (Set Price)	8	Each	140.00	

SCHEDULE OF PRICES

PROJECT: 596-25, 26; 93rd St. North between Meridian & Broadway (R338)

TYPE OF WORK: Grading, RCC Surfacing, RCB Culvert, Guardrail, Pavement Marking, Seeding

Bidding Item	Approx. Quantity	Unit	Unit Price	Amount
Temporary Seeding	1	Lump Sum		
Seeding	1	Lump Sum		
Silt Fence	6,250	L.F.		
Sediment Removal (Set Price)	1	Cu. Yds.	35.00	
Temporary Berm (Set Price)	1	L.F.	1.00	
Temporary Ditch Check (Rock)	1	Cu. Yds.	85.00	
Water (Erosion Control)(Set Price)	1	M. Gal	35.00	
Pavement Marking (Paint) (White) (4")	19,462	L.F.		
Pavement Marking (Paint) (Yellow) (4")	8,329	L.F.		
Guardrail, Steel Plate	50	L.F.		
Guardrail End Terminal (SKT)	4	Each		
Traffic Control	1	Lump Sum		
Work Zone Sign Special (G-20)	2	Each		
Grand Total				

DOLLARS

Company or Firm Name

BY

TITLE