

ADDENDUM NO. 1

Sedgwick County Project: 839-R-979; Bridge on 143rd St. East
between Harry & Pawnee (B490)


The items contained herein now become a part of the referenced plans and specifications. Please read the following items and acknowledge receipt of this addendum on the Proposal Page Number P-1. NOTE: THIS ADDENDUM MUST BE ACKNOWLEDGED TO CONSTITUTE A VALID BID.

SPECS:

Replace page SOP-1 to 2 with pages SOP-1R to 2R.

PLANS:

N/A

By: 
FOR David C. Spears, P.E.,
Director/County Engineer

Date: February 21, 2020

SCHEDULE OF PRICES

PROJECT: 839-R-979; Bridge on 143rd St. East between Harry & Pawnee (B490)

TYPE OF WORK: RCB Bridge, Grading, Surfacing (Asphalt), Seeding

Bidding Item	Approx. Quantity	Unit	Unit Price	Amount
GRADING ITEMS:				
Clearing and Grubbing	1	Lump Sum		
Removal of Existing Structure	1	Lump Sum		
Common Excavation (Contractor Furnished)(VMF=0.75)	1,543	Cu. Yds.		
Common Excavation(VMF=0.75)	1,013	Cu. Yds.		
Compaction of Earthwork (Type B)(MR-90)	1,917	Cu. Yds.		
Water (Grading)(Set Price)	1	M. Gals.	35.00	
Mobilization	1	Lump Sum		
Field Office (Type A)	1	Each		
Slope Protection (RIPRAP STONE)(100 Lbs.)	324	Sq. Yd.		
Temporary Surfacing Material (Aggregate)(Set Price)	1	Cu. Yds.	35.00	
Aggregate Base (Special)(6")	2,044	S.Y.		
Entrance Pipe (30")(RCP)	241	Lin. Ft.		
Guardrail, Steel Plate	212.5	Lin. Ft.		
End Terminals (SKT or ET Plus)	4	Each		
Signing (Object Marker)(Type 3)	4	Each		
Contractor Construction Staking	1	Lump Sum		
Sidewalk Construction (6")(AE)	356.5	Sq. Yd.		
Rock Excavation (Existing Pavement)	236.0	Cu. Yds.		
Plant Mix Asphalt Mixture - Comm. Grade (Class A) (8")	938	Ton		
Work Zone Camara System Installed	1	Each		
TEMPORARY EROSION & POLLUTION CONTROL:				
Temporary Seeding	1	Lump Sum		
Temporary Berm (Set Price)	1	Lin. Ft.	1.10	
Silt Fence (Set Price)	1	Lin. Ft.	4.00	
Biodegradable Log (9")	94	Lin. Ft.		
Biodegradable Log (12")	75	Lin. Ft.		
Temporary Ditch Check (Rock)	21	Cu. Yds.		
Temporary Ditch Check	158	Lin. Ft.		
Sediment Removal (Set Price)	1	Cu. Yds.	35.00	
Mobilization, Emergency Erosion Control (Set Price)	1	Each	1,000.00	
Erosion Control (Class I, Type C)	2,403	Sq. Yd.		
Mulching (Temporary)	1.2	Ton		
Water (Erosion Control)(Set Price)	1	M.Gal.	35.00	
PERMANENT SEEDING:				
Seeding	1	Lump Sum		

SCHEDULE OF PRICES

PROJECT: 839-R-979; Bridge on 143rd St. East between Harry & Pawnee (B490)

TYPE OF WORK: RCB Bridge, Grading, Surfacing (Asphalt), Seeding

Bidding Item	Approx. Quantity	Unit	Unit Price	Amount
TRAFFIC CONTROL:				
Traffic Control	1	Lump Sum		
BRIDGE: 4 - 10'x 10'x 57'-9" R.C.B.				
Concrete (Grade 4.0)(AE)	329.5	Cu. Yds.		
Reinforcing Steel (Grade 60)(Epoxy Coated)	66,980	Lbs.		
Class III Excavation	1,107	Cu. Yds.		
Foundation Stabilization	65	Cu. Yds.		
Concrete for Seal Course (Set Price)	1	Cu. Yds.	175.00	
Granular Backfill (Wingwalls)	186	Cu. Yds.		
Bridge Backwall Protection System	277	Sq. Yd.		
Handrail (Special) (4'-6")	85	Lin. Ft.		
Handrail (Special) (1'-10")	44	Lin. Ft.		
Concrete Form Liner	22.0	Sq. Yd.		
Grand Total				

In Words:

DOLLARS

Company or Firm Name

BY

TITLE