

SUMMARY OF QUANTITIES

Project: 2021 BM-1 Overlays (R175-E)

Type of Work: Asphalt Overlay, Milling and Pavement Marking

Items	Approx. Quantity	Unit
Mobilization	1	L.S.
Bituminous Surface Construction (BM-1)	19,690	Tons
Plant Mix Asphalt Mixture - Commercial Grade	244	Tons
Transition Milling	2,955	SqYd
Edge Milling	7,100	SqYd
Rumble Strips (Milled)(Asphalt)(Centerline)	66.0	Sta.
Pavement Marking (Thermoplastic)(White)(4")	247,601	L.F.
Pavement Marking (Thermoplastic)(White)(6")	730	L.F.
Pavement Marking (Thermoplastic)(White)(16")	50	L.F.
Pavement Marking (Thermoplastic)(White)(24")	40	L.F.
Pavement Marking (Thermoplastic)(Yellow)(4")	55,910	L.F.
Pavement Marking (Thermoplastic)(Yellow)(12")	304	L.F.
Pavement Marking Symbol (Thermoplastic)(White)(Left Arrow)	12	Each
Pavement Marking Symbol (Thermoplastic)(White)(Right Arrow)	7	Each
Traffic Control	1	L.S.