

## SUMMARY OF QUANTITIES

**Project No.: 2023 NovaChip (R175-B)**

**Type of Work: Ultrathin Bonded Asphalt Surface & Pavement Marking**

Items	Approx. Quantity	Unit
Mobilization	1	LSUM
HMA Surface (Ultrathin Bonded)(Type A)(PG64-22)	40,674	TONS
Milling	29,349	S.Y.
Rumble Strips (Milled)(Asphalt)(Centerline)	99	Sta
Rumble Strips (Milled)(Asphalt)(Shoulder)	20	Sta
Adjustment of Valve Box	2	Each
Adjustment of Manhole	4	Each
Thermoplastic Pavement Marking (White)(4")(0.090")	707,157	L.F.
Thermoplastic Pavement Marking (White)(6")(0.090")	3,582	L.F.
Thermoplastic Pavement Marking (White)(12")(0.125")	64	L.F.
Thermoplastic Pavement Marking (White)(16")(0.125")	472	L.F.
Thermoplastic Pavement Marking (White)(24")(0.125")	663	L.F.
Thermoplastic Pavement Marking (Yellow)(4")(0.090")	269,032	L.F.
Thermoplastic Pavement Marking (Yellow)(12")(0.125")	1,033	L.F.
Thermoplastic Pavement Marking (White)(Left Arrow)(0.125")	48	Each
Thermoplastic Pavement Marking (White)(Right Arrow)(0.125")	6	Each
Thermoplastic Pavement Marking (White)(Railroad Crossing)(0.125")	13	Each
Thermoplastic Pavement Marking (White)(Bike)(0.125")	6	Each
Traffic Control	1	LSUM