

## SUMMARY OF QUANTITIES

**PROJECT: Dry Creek Estates; Street Improvements**

**TYPE OF WORK: RCB Culvert, Surfacing (Asphalt), Grading, Seeding, Pond Grading, Signing**

Items	Approx. Quantity	Unit
Contractor Construction Staking	1	LSUM
Mobilization	1	LSUM
Clearing and Grubbing	1	LSUM
Common Excavation	39,810	C.Y.
Compaction of Earthwork (Type B, MR-90)	28,050	C.Y.
Water (Grading) (Set Price)	1	MGAL
Temporary Seeding	1	LSUM
Seeding	1	LSUM
Sediment Removal (Set Price)	1	C.Y.
Erosion Control (Class 1) (Type D)	380	S.Y.
Temporary Berm (Set Price)	1	L.F.
Biodegradable Log (20")	1,504	L.F.
Silt Fence	3,335	L.F.
Water (Erosion Control) (Set Price)	1	MGAL
SWPPP Design	1	LSUM
Foundation Stabilization	47	C.Y.
Granular Backfill (Wingwalls)	24	C.Y.
Concrete for Seal Course (Set Price)	1	C.Y.
Concrete (Grade 4.0) (AE)	48.6	C.Y.
Concrete (Grade 4.0)	87.4	C.Y.
Reinforcing Steel (Grade 60)	1,440	LBS
Reinforcing Steel (Grade 60) (Epoxy Coated)	26,320	LBS
Bridge Backwall Protection System	207	S.Y.
Cross Road Pipe (30") (RCP)	138	L.F.
Cross Road Pipe (36") (RCP)	186	L.F.
Cross Road Pipe (2.0 Sq. Ft.) (RCPHE)	56	L.F.
End Section (30") (RC)	6	EACH
End Section (36") (RC)	6	EACH
End Section (2.0 Sq. Ft.) (RCHE)	2	EACH
Riprap (Light Stone)	1,883	S.Y.
Concrete Backslope Ditch Lining	12	S.Y.

Items	Approx. Quantity	Unit
Mailbox Installation (Set Price)	2	EACH
Aggregate Base (AB-3) (6")	207	S.Y.
Aggregate Base (Special) (6")	20,638	S.Y.
Aggregate Shoulder AS-1 (6")	4,521	S.Y.
Water (Aggregate Base) (Set Price)	1	MGAL
Plant Mix Asphalt Mixture - Commercial Grade (Surface) (2")	1,675	TON
Plant Mix Asphalt Mixture - Commercial Grade (Base) (4")	3,349	TON
Signing Object Marker (Type 3) (Double)	10	EACH
Signing Object Marker (Type 3)	4	EACH
Sign (Flat Sheet) (High Performance)	51	S. F.
Sign Post Footing (1-3/4" Perforated Square Steel Tube)	2	EACH
Sign Post (1-3/4" Perforated Square Steel Tube)	26	L.F.
Sign Post (2 lb/ft "U" Steel)	278	L.F.
Traffic Control	1	LSUM