

**ADDENDUM NO. 1**

**Sedgwick County Project: 835-B-3186; Bridge on Greenwich Road, between 109th and 117th Streets North (B502)**

**The items contained herein now become a part of the referenced plans and specifications. Please read the following items and acknowledge receipt of this addendum on the Proposal Page Number P-1. NOTE: THIS ADDENDUM MUST BE ACKNOWLEDGED TO CONSTITUTE A VALID BID.**

***SPECS:***

- Replace SOP-1 with SOP-1R (Added Unit Price for all Bid Items labeled as “(Set Price)”)

By: 

Lynn T. Packer, P.E.

Director of Public Works/County Engineer

**Date: June 6, 2023**

**SCHEDULE OF PRICES**

**Project: 835-B-3186: Bridge on Greenwich Road, between 109th and 117th Streets North (B502)**

**Type of Work: RCB Bridge Construction, Asphalt Surfacing, Grading, Guardrail, Pavement Marking, Seeding**

ITEM	QUANTITY	UNIT	UNIT PRICE	AMOUNT
Clearing and Grubbing	1	LSUM		
Removal of Existing Structures	1	LSUM		
Mobilization	1	LSUM		
Field Office	1	LSUM		
Contractor Construction Staking	1	LSUM		
Common Excavation	456	CY		
Common Excavation (Contractor Furnished)	2,569	CY		
Rock Excavation	69	CY		
Compaction of Earthwork (Type B)(MR 90)	2,209	CY		
Water (Grading)(Set Price)	1	MGAL	\$ 35.00	\$ 35.00
Plant Mix Asphalt Mixture - Commercial Grade (7")	265	TONS		
Aggregate Base (Special)(6")	717	SY		
Guardrail, Steel Plate (MGS)	275	LF		
Guardrail End Terminal (MGS-MSKT)	4	EACH		
Entrance Pipe (18")(RCP)	48	LF		
End Section (18")(RC)	2	EACH		
Concrete (Grade 4.0)	161	CY		
Concrete (Grade 4.0) (AE)	82	CY		
Reinforcing Steel (Gr. 60)	36,110	LB		
Reinforcing Steel (Gr. 60) (Epoxy Coated)	27,520	LB		
Class III Excavation	1,370	CY		
Foundation Stabilization	65	CY		
Concrete For Seal Course (Set Price)	1	CY	\$ 175.00	\$ 175.00
Granular Backfill (Wingwalls)	192	CY		
Bridge Backwall Protection System	181	SY		
Aggregate for Shoulders (AS-1)(6")	192	TONS		
Surfacing Material (AB-3)(4")	41	TONS		
Water Aggregate Shoulder (Set Price)	1	MGAL	\$ 35.00	\$ 35.00
Aggregate Ditch Lining (6")	229	TONS		
Riprap (Light Stone)(100 lb)	288	SY		
Temporary Seeding	1	LS		
Sediment Removal (Set Price)	1	LS	\$ 35.00	\$ 35.00
Temporary Berm (Set Price)	1	LF	\$ 1.00	\$ 1.00
Biodegradable Log (20")	75	LF		
Silt Fence	1,605	LF		
SWPPP Design	1	LS		
Water (Erosion Control)(Set Price)	1	MGAL	\$ 35.00	\$ 35.00
Seeding	1	LS		
Traffic Control	1	LS		
Pavement Marking (Thermoplastic)(White)(4")	2,036	LF		
Pavement Marking (Thermoplastic)(Yellow)(4")	320	LF		
Object Marker (OM-3)	4	EACH		
<b>GRAND TOTAL</b>				

In Words:

DOLLARS

\_\_\_\_\_  
Company or Firm Name

\_\_\_\_\_  
BY

\_\_\_\_\_  
TITLE