

**SUMMARY OF QUANTITIES**

**PROJECT: Webb Road between 79th and 87th Streets South (R367)**

**TYPE OF WORK:Grading, Surfacing, Subgrade Modification, Seeding, and Pavement Marking**

Items	Approx. Quantity	Unit
Contractor Construction Staking	1	LSUM
Mobilization	1	LSUM
Removal of Existing Structures	1	LSUM
Clearing and Grubbing	1	LSUM
Common Excavation	5,275	C.Y.
Common Excavation (Contractor Furnished)	347	C.Y.
Compaction of Earthwork (Type B) (MR-90)	4,498	C.Y.
Water (Grading) (Set Price)	1	MGAL
Aggregate Base (Special)(5")	12,874	S. Y.
Water (Aggregate Base)(Set Price)	1	MGAL
Surfacing Material (AB-3)	80	TONS
Plant Mix Asphalt Mixture-Commercial Grade (Base)(2 1/2")	1,994	TONS
Plant Mix Asphalt Mixture-Commercial Grade (Surface)(1 1/2")	1,095	TONS
Plant Mix Asphalt Mixture-Commercial Grade (Entrances)(Base)(6'	374	TONS
Crossroad Pipe (3.0 Sq. Ft.) (RCPHE)	24	L. F.
Crossroad Pipe (7.0 Sq. Ft.) (RCPHE)	60	L. F.
Entrance Pipe (1.5 Sq. Ft.) (RCPHE)	322	L. F.
Entrance Pipe (7.0 Sq. Ft.) (RCPHE)	36	L. F.
End Section (1.5 Sq. Ft.) (RCHE)	18	EA.
End Section (7.0 Sq. Ft.) (RCHE)	4	EA.
Resetting End Section (3.0 Sq. Ft.)(RCHE)	4	EA.
Mailbox Installation (Set Price)	9	EA.
Seeding	1	LSUM
Temporary Seeding	1	LSUM
Sediment Removal (Set Price)	1	C.Y.
Temporary Berm (Set Price)	1	C.Y.
Biodegradable Log (20")	2,720	L. F.
Silt Fence	1,215	L. F.
SWPPP	1	L.S.
Water (Erosion Control) (Set Price)	1	MGAL
Traffic Control	1	LSUM
Thermoplastic Pavement Marking (White)(4") (0.090")	8,600	L. F.
Thermoplastic Pavement Marking (Yellow)(4") (0.090")	1,070	L. F.
Pavement Marking (Methyl Methacrylate)(White)(4")(0.090")	246	L. F.
Pavement Marking (Methyl Methacrylate)(Yellow)(4")(0.090")	30	L. F.