

## SUMMARY OF QUANTITIES

**PROJECT: Stonewater Addition; Paving Improvements Phase 1**

**TYPE OF WORK: Asphalt Surfacing and Grading**

Items	Approx. Quantity	Unit
Contractor Construction Staking	1	LSUM
Mobilization	1	LSUM
Clearing and Grubbing	1	LSUM
Common Excavation	6,462	C.Y.
Compaction of Earthwork (Type B)(MR-90)	4,466	C.Y.
Water (Grading)(Set Price)	1	MGAL
Aggregate Base (Special)(6")	18,326	S.Y.
Aggregate Shoulder (AB-3)(4")	4,401	S.Y.
Water (Aggregate Base)(Set Price)	1	MGAL
Plant Mix Asphalt Mixture-Commercial Grade (Base)	3,342	TON
Plant Mix Asphalt Mixture-Commercial Grade (Surface)	1,595	TON
Traffic Control	1	LSUM
Sign (Flat Sheet) (High Performance)	247.01	SF
Sign Post (1 3/4" Perforated Square Steel Tube)	146	L.F.
Sign Post (2 1/4" Perforated Square Steel Tube)	24	L.F.
Sign Post Footing (2" Perforated Square Steel Tube)	48	EACH
Sign Post (2 LB/FT "U" Steel)	463	L.F.