

SUMMARY OF QUANTITIES

PROJECT: Rachel Brooke Estates Addition; Drainage & Infrastructure Improvements

TYPE OF WORK: Grading, Drainage, Erosion Control, Precast Culvert, Seeding

Bidding Item	Approx. Quantity	Unit
Removal of Existing Structures	1	LS
Mobilization	1	LS
Contractor Construction Staking	1	LS
Clearing and Grubbing	1	LS
Common Excavation	99,170	CY
Compaction of Earthwork (Type AA)(MR-3-3)	11,530	CY
Compaction of Earthwork (Type B)(MR-90)	22,105	CY
Reinforced Concrete Box (10'x3') (Precast)	174	LF
Reinforced Concrete Box (7'x3') (Precast)	139	LF
End Section (21.0 SQ FT)	3	EA
End Section (30.0 SQ FT)	6	EA
Storm Sewer (30") (RCP)	95	LF
End Section (30")(RC)	2	EA
Manhole (Reinforced Concrete)	1	EA
Inlet (Manhole)(Special)	1	EA
Riprap (Light Stone)(100 lb)	209	SY
Granular Base - Granular Type 2	17	SY
Gabion Basket (9'x3'x3')	32	EA
Gabion Mattress (9'x3'x0'-9")	56	EA
Erosion Control (Class 1)(Type C)	1,978	SY
Erosion Control (Class 2)(Type H)	710	SY
Silt Fence	21,725	LF
Ditch Check	59	EA
Temporary Seeding	1	LS
Mulching	81	Ton
Seeding	1	LS

SWPPP Design	1	LS
Water (Grading)(Set Price)	1	Mgal
Water (Erosion Control)(Set Price)	1	Mgal
Temporary Berm (Set Price)	1	LF
Sediment Removal (Set Price)	1	CY
Traffic Control	1	LS