

SUMMARY OF QUANTITIES

PROJECT: **Street and Drainage Improvements; to Serve Brinley Estates**

TYPE OF WORK: **Grading, Asphalt Surfacing, Seeding**

Bidding Item	Approx. Quantity	Unit
CONTRACTOR CONSTRUCTION STAKING	1	LS
MOBILIZATION	1	LS
CLEARING AND GRUBBING	1	LS
COMMON EXCAVATION	24,806	CY
COMPACTION OF EARTHWORK (TYPE B) (MR-90)	23,346	CY
EMBANKMENT (CONTRACTOR FURNISHED)	2,000	CY
WATER (GRADING) (SET PRICE)	1	MG
CROSS ROAD PIPE (18") (RCP)	192	LF
CROSS ROAD PIPE (24") (RCP)	110	LF
CROSS ROAD PIPE (30") (RCP)	141	LF
CROSS ROAD PIPE (36") (RCP)	109	LF
END SECTION (18") (RC)	6	EA
END SECTION (24") (RC)	4	EA
END SECTION (30") (RC)	4	EA
END SECTION (36") (RC)	4	EA
RIPRAP (LIGHT STONE)	416	SY
TEMPORARY FERTILIZER (15-30-15)	750	LB
TEMPORARY SEEDING	1	LS
SEEDING	1	LS
SOIL EROSION MIX	12	LB
EROSION CONTROL (CLASS 2) (TYPE H)	8,400	SY
SEDIMENT REMOVAL (SET PRICE)	1	CY
TEMPORARY BERM (SET PRICE)	1	LF
BIODEGRADABLE LOG (20")	1,043	LF
SILT FENCE	2,710	LF
SWPPP DESIGN	1	LS

MULCH TACKING SLURRY	10,260	LB
MULCHING	23	TON
WATER (EROSION CONTROL) (SET PRICE)	1	MG
AGGREGATE BASE (SPECIAL) (6")	15,686	SY
AGGREGATE SHOULDER (AB-3) (4")	4,156	SY
WATER (AGGREGATE BASE) (SET PRICE)	1	MG
PLANT MIX ASPHALT MIXTURE - COMMERCIAL GRADE	4,151	TON
TRAFFIC CONTROL	1	LS
SIGN (FLAT SHEET) (HIGH PERFORMANCE)	176	SF
SIGN POST (1 3/4" PERFORATED SQUARE STEEL TUBE)	373	LF
SIGN POST (2 1/4" PERFORATED SQUARE STEEL TUBE)	50	LF
SIGN POST FOOTING (2" PERFORATED SQUARE STEEL TUBE)	33	EA
SIGN POST (2 LB/FT "U" STEEL)	27	LF