

SUMMARY OF QUANTITIES

PROJECT: Culvert Replacement on S. Rock Road, North of E. 47th S.
(R264-124)

TYPE OF WORK: Asphalt Surfacing, Culvert, Traffic Control, Pavement Marking

Bidding Item	Approx. Quantity	Unit
Contractor Construction Staking	1	L.S.
Mobilization	1	L.S.
Removal of Existing Structures	1	L.S.
Common Excavation	147	Cu. Yd.
Rock Excavation	44	Cu. Yd.
Water (Grading)(Set Price)	1	M-Gal
Flowable Fill	260	Cu. Yd.
Aggregate Base (Special)(6")	214	S.Y.
Water (Aggregate Base)(Set Price)	1	M-Gal
Cross Road Pipe (10.0 Sq. Ft.)(RCPHE)	94	L.F.
End Section (10.0 Sq. Ft.)(RC)	2	Each
HMA Commercial Grade (Class A)	101	Tons
Milling	333	S.Y.
Aggregate Shoulders (AS-1) (6")	25	Tons
Water (Aggregate Shoulders)(Set Price)	1	M-Gal
Seeding	1	L.S.
Pavement Marking (Thermoplastic)(White)(4")(0.090")	3760	L.F.
Pavement Marking (Thermoplastic)(White)(6")(0.090")	1890	L.F.
Pavement Marking (Thermoplastic)(White)(24")(0.125")	96	L.F.
Pavement Marking (Thermoplastic)(Yellow)(4")(0.090")	4337	L.F.
Pavement Marking (Thermoplastic)(Yellow)(18")(0.090")	104	L.F.
Pavement Marking (Thermoplastic)(White)(Left Turn Arrow)(0.125")	4	Each
Traffic Control	1	L.S.

