

ADDENDUM NO. 1

**Sedgwick County Project: 630-28-2750 (47th) & 598-22-5261(85th);
Major Bridge Maintenance (B520)**

The items contained herein now become a part of the referenced plans and specifications. Please read the following items and acknowledge receipt of this addendum on the Proposal Page Number P-1. NOTE: THIS ADDENDUM MUST BE ACKNOWLEDGED TO CONSTITUTE A VALID BID.

SPECS:

- Replace SOP-1 to 2 with SOP-1R to 2R: Added Set Price Pricing

PLANS:

- Clarification statement: Bridge Repair (LS) is as described in the General Notes and is limited to the work described for filling the void/cavity areas behind the abutment sidewalls at all four corners, including drilling and placement of flowable fill (estimated quantity noted for information only). It does not extend to include other parts of the bridge.

By: _____


Lynn T. Packer, P.E.


Director of Public Works/County Engineer

Date: January 20, 2026

SCHEDULE OF PRICES

PROJECT: 630-28-2750 (47th) & 598-22-5261(85th); Major Bridge Maintenance (B520)
TYPE OF WORK: Approach Slab Bridge Repair

Bidding Item	Approx. Quantity	Unit	Unit Price	Amount
Base Bid - 47th Street				
<i>Mobilization</i>	1	LS		
<i>Rock Excavation</i>	8	CY		
<i>Concrete Pavement (12" Uniform) (AE)(Br App)</i>	24.5	SY		
<i>Reinforcing Steel (Grade 60) (Epoxy Coated)</i>	256	LBS		
<i>Area Prepared for Patching</i>	11	SY		
<i>Area Prepared for Patching (Full Depth)</i>	1	SY		
<i>Reinforcing Steel (Repair)(Grade 60)(Set Price)</i>	1	LBS	\$3.00	\$3.00
<i>Reinforcing Steel (Repair)(Grade 60)(Epoxy) (Set Price)</i>	1	LBS	\$4.00	\$4.00
<i>Bridge Repair</i>	1	LS		
<i>Traffic Control</i>	1	LS		
Additive - 47th Street				
<i>Rock Excavation</i>	8	CY		
<i>Concrete Pavement (12" Uniform) (AE)(Br App)</i>	23.3	SY		
<i>Reinforcing Steel (Grade 60) (Epoxy Coated)</i>	256	LBS		
Base Bid - 85th Street				
<i>Mobilization</i>	1	LS		
<i>Rock Excavation</i>	30	CY		
<i>Guardrail, Removal and Reconstruction of Steel Plate</i>	50	LF		
<i>Drilling and Grouting</i>	29	EA		
<i>Concrete Pavement (11 13/16" Uniform)(AE)(Br App)</i>	74.1	SY		
<i>Reinforcing Steel (Grade 60)(Epoxy Coated)</i>	3352	LBS		
<i>Traffic Control</i>	1	LS		
<i>Bridge Approach Slab Footing</i>	11.9	CY		
Additive - 85th Street				
<i>Rock Excavation</i>	3	CY		
<i>Concrete Pavement (11 13/16" Uniform) (AE)(Br App)</i>	8.9	SY		



<i>Reinforcing Steel (Grade 60) (Epoxy Coated)</i>	18	LBS		
GRAND TOTAL				

In Words:

DOLLARS

CENTS

Company or Firm Name

BY

TITLE

1

1/20/2026: Added Set Price Pricing