SUMMARY OF QUANTITIES

PROJECT: **634-13-4224; W 63rd St. S Over Tributary to Spring Creek (B523)**

TYPE OF WORK: PreCast Concrete Beam Bridge, Guardrail

Bidding Item	Approx. Quantity	Unit
Contractor Construction Staking	1	Lump Sum
Field Office	1	Each
Foundation Stabilization (Set Price)	1	Cu. Yds
Mobilization	1	Lump Sum
Removal of Existing Structures	1	Lump Sum
Concrete for Seal Course (Set Price)	1	Cu. Yds
Clearing and Grubbing	1	Lump Sum
Common Excavation	1016	Cu. Yds
Compaction of Earthwork (Type B)(MR-90)	445	Cu. Yds
Water (Grading)(Set Price)	1	M.Gal.
Temporary Surfacing Material (Agg.)(Set Price)	1	Cu. Yds
Guardrail Steeel Plate	212.5	Lin. Ft.
Guardrail End Section (FLEAT)	4	Each
Signing Object marker (Type 3)	4	Each
Class I Excavation	86	Cu. Yds.
Class II Excavation	190	Cu. Yds.
Precast Reinforced Concrete Bridge Slabs	1768	Sq, Ft.
Concrete (Grade 4.0)(AE)	86	Cu. Yds.
Reinforcing Steel (Gr. 60)	7220	Lbs.
Steel Piles (HP 12x53)	440	Lin. Ft.
Cast Steel Pile Holes	20	Each
Pre-Drilled Pile Holes	300	Lin. Ft.
Contractor Furnished PDA	2	Each
Slope Protection (Riprap)(Light Stone)(200Lb.)	70	Cu. Yds.

Seeding	1	Lump Sum
Erosion Control (Class 1, Type C)	2670	Sq. Yds.
Sediment Removal (Set Price)	1	Cu. Yds.
Temporary Berm (Set Pice)	1	Lin. Ft.
Silt Fence	1100	Lin. Ft.
Water (Erosion Control)(Set Price)	1	M. Gal.
Aggregate Base (AB-3)(6")	1321	Sq. Yds.
Surfacing Material (SA-X)	148	Ton
Traffic Control	1	Lump Sum