RFB# 26-0100

ADDENDUM NO. 1

Sedgwick County Project: **805-E-3200; N 119th St. W Bridge Over Eagle Drainage Ditch (B527)**

The items contained herein now become a part of the referenced plans and specifications. Please read the following items and acknowledge receipt of this addendum on the Proposal Page Number P-1. NOTE: THIS ADDENDUM MUST BE ACKNOWLEDGED TO CONSTITUTE A VALID BID.

SPECS

- Replace SOP-1 to 2 with SOP-1R to 2R: Changed the bid item "Piles (Steel)" from HP24x35 to HP12x35.

By: _____
Lynn T. Packer, P.E.
Director of Public Works/County Engineer

Date: November 23, 2026

SCHEDULE OF PRICES

PROJECT: **805-E-3200; N 119th ST. W Bridge Over Eagle Drainage Ditch (B527)**
TYPE OF WORK: **RCSH Span Bridge, Grading, Guardrail**

Bidding Item	Approx. Quantity	Unit	Unit Price	Amount
Contractor Construction Staking	1	LS		
Field Office	1	LS		
Mobilization	1	LS		
Removal of Existing Structures	1	LS		
Clearing and Grubbing	1	LS		
Common Excavation	2,897	CY		
Compactin of Earthwork (Type B) (MR90)	1,127	CY		
Water (Grading) (SetPrice)	1	Mgal	$40.00	
Concrete Pavement (10" Uniform)(AE)(BR App)	81	SY		
Aggregate Base (AB-3)(6")	1,766	SY		
Aggregate Base (Special)(6")	87	SY		
Water (Aggregate Base)(Set Price)	1	Mgal	$40.00	
Surfacing Material (SA-X)	173	TON		
Surfacing Material (AB-3)(6")	78	TON		
Storm Sewer (18")(RCP)	33	LF		
Storm Sewer (30")(RCP)	35	LF		
Storm Sewer (36")(RCP)	33	LF		
Storm Sewer (42")(RCP)	40	LF		
Entrance Pipe (18")(RCP)	37	LF		
Entrance Pipe (30")(RCP)	39	LF		
End Section (18")(RC)	3	Each		
End Section (30")(RC)	3	Each		
End Section (36")(RC)	1	Each		
End Section (42")(RC)	1	Each		
Headwall Structure (18")	1	Each		
Headwall Structure (30")	1	Each		
Headwall Structure (36")	1	Each		
Headwall Structure (42")	1	Each		
Guardrail, Steel Plate	225	LF		
Guardrail End Terminal (MGS-FLEAT)	4	Each		
Riprap (Light Stone)(100 LB)	591	SY		
Class I Excavation	63	CY		

Class II Excavation	88	CY		
Concrete (Grade 4.0)(AE)(SW)	214	CY		
Concrete (Grade 4.0)(AE)	37	CY		
Reinforcing Steel (Gr. 60)	2,780	LB		
Reinforcing Steel (Gr. 60)(Epoxy Coated)	58,700	LB		
Piles (Steel)(HP12x53)	1,050	LF		
Test Piles (Special)(HP12x53)	138	LF		
Bridge Backwall Protection System	36	SY		
Abutment Strip Drain	32	SY		
Erosion Control (Class 1)(Type D)	510	SY		
Sediment Removal (Set Price)	1	CY	$65.00	
Temporary Berm (Set Price)	1	LF	$2.00	
Temporary Ditch Check (Tock)	46	CY		
Biodegradable Log (20")	118	LF		
Silt Fence	241	LF		
SWPPP Design	1	LS		
Temporary Seeding	1	LS		
Water (Erosion Control)(Set Price)	1	Mgal	$40.00	
Seeding	1	LS		
Object Marker (OM-3)	4	Each		
Traffic Control	1	LS		
			GRAND TOTAL	

1

In Words:

DOLLARS

CENTS

Company or Firm Name

BY

TITLE

1 11/23/2026: Changed "Piles (Steel)" from HP24x35 to HP12x35